Column schedule								Column Volume			Column forming area		
	LENGTH		WIDTH		HEIGHT				TOTAL		forming	Total	
MARK	FEET	INCHES	FEET	INCHES	FEET	INCHES	OTY.	VOLUME	VOLUME		area	forming	
C3*	16ø				5	0	2	7	14		21	42	
								total	14	CU.FT		42	SQ.FT

Tie-Column schedule								Column Volume			Column forming area		
	LENGTH		WIDTH		HEIGHT				TOTAL		forming	Total	
MARK	FEET	INCHES	FEET	INCHES	FEET	INCHES	OTY.	VOLUME	VOLUME		area	forming	
TC5		8		24	5	0	3	7	20		27	80	
TC6*		24		8	5	0	2	7	13		27	53	
								total	20	CU.FT		133	SQ.FT

Grid marked-Column schedule								Column Volume			Column forming area		
	LENGTH		WIDTH		HEIGHT				TOTAL		forming	Total	
MARK	FEET	INCHES	FEET	INCHES	FEET	INCHES	OTY.	VOLUME	VOLUME		area	forming	
WEST													
A-1*	16ø				5	0	1	7	7		21	21	
A-2		16		24	5	0	1	13	13		33	33	
A-3		16		24	5	0	1	13	13		33	33	
A-6		16		18	5	0	1	10	10		28	28	
A-7		16		24	5	0	1	13	13		33	33	
A-8		16		24	5	0	1	13	13		33	33	
A-9		16		24	5	0	1	13	13		33	33	
A-11		16		24	5	0	1	13	13		33	33	
A-12		16		24	5	0	1	13	13		33	33	
C-1	16ø				5	0	1	7	7		21	21	
C-2		16		24	5	0	1	13	13		33	33	
C-3		16		24	5	0	1	13	13		33	33	
C-7		16		24	5	0	1	13	13		33	33	
C-8		16		24	5	0	1	13	13		33	33	
C-9		16		24	5	0	1	13	13		33	33	
C-11		16		24	5	0	1	13	13		33	33	
C-12		16		24	5	0	1	13	13		33	33	
E-1	16ø				5	0	1	7	7		21	21	
E-2		16		24	5	0	1	13	13		33	33	
G-1	16ø				5	0	1	7	7		21	21	
G-2		16		24	5	0	1	13	13		33	33	
G-3		16		24	5	0	1	13	13		33	33	
H-7		16		24	5	0	1	13	13		33	33	
H-8		16		24	5	0	1	13	13		33	33	
H-9		16		24	5	0	1	13	13		33	33	
H-11		16		24	5	0	1	13	13		33	33	
I-6		16		24	5	0	1	13	13		33	33	
I-7		16		24	5	0	1	13	13		33	33	
I-8		16		24	5	0	1	13	13		33	33	
I-9		16		24	5	0	1	13	13		33	33	
I-11		16		24	5	0	1	13	13		33	33	
I-12		16		24	5	0	1	13	13		33	33	

Column Reinforcing (foundation)			
Dia	total length	Unit wt	total wt.
#3	12,054.00	0.376	4532.304
#5	80.00	1.04	83.44
#6	120.00	1.50	180.24
#7	1,670.00	2.04	3,413.48
#8	60.00	2.67	160.20
#9	1,090.00	3.40	3,706.00
#10	2,170.00	4.30	9,331.00